



April 2, 2018

To: Perspective Bidders

Subject: Addendum Two: Corrections to Project Manual and Item Bid List

Project: NC 751 NC 54 Sidewalk Construction Contract from Dresden Dr to Garrett Rd (U-4726HJ/SW-30)

- I. In the Project Manual’s Table of Contents please strike the following sections:
 - a. Asphalt Binder Content of Asphalt Plant Mixes
 - b. Steel Plate Drainage Item
 - c. Concrete Steps
 - d. Modified Concrete Flume with Concrete Outlet
- II. In the General Provisions section the Intermediate Contract Time (ICT) Number 1 does permit work at night on Monday, Tuesday, Wednesday, and Thursday; however, Addendum One, dated March 7, 2018, in the Additional Information section, Item 3 states, “There will be no night or Sunday work on the project”. Please note that Addendum One supersedes the provisions of ICT #1 and no night work will be allowed.
- III. In the Project Special Provisions – Roadway section please add the following Special Provision:

GREEN VINYL COATED CHAIN LINK FENCE:

(1-1-02) (Rev.7-18-06)

SPI 8-

Description

Provide green vinyl coated chain link fence in accordance with the plans and Article 1050-6 of the *2012 Standard Specifications*.

Materials

Provide materials that meet the requirements of Article 866-2 of the *Standard Specifications*

Construction Methods

Construct the green vinyl coated chain link fence in accordance with Article 866-3 of the *Standard Specifications*

Measurement and Payment

Green Vinyl Coated Chain Link Fence, ___" Fabric, Green Vinyl Costed Metal Terminal Post for ___" Chain Link Fence, and Green Vinyl Coated Metal Line Post for ___" Chain Link Fence will be measured and paid for in accordance with Article 866-4 of the *Standard Specifications*.

Payment will be made under:

Pay Item

Green Vinyl Coated, Chain Link Fence, 48” Fabric
Green Vinyl Coated Metal Terminal Post for 48” Chain Link Fence
Green Vinyl Coated Metal Line Post for 48” Chain Link Fence

Pay Unit

LF
EA
EA



- IV. Please find attached the revised Item Sheets for bidding which has been revised thusly:
- a. Line # 0004, #57 STONE FOR TREE PROTECTION is hereby removed.
 - b. Line # 0016 is hereby renamed from 6" CONCRETE DRIVEWAY to 6" CONCRETE DRIVEWAY, 6" CONCRETE SIDEWALK, & 6" CONCRETE SLOPE PROTECTION W/ 6" CURB
 - c. The quantity for Line # 0016 is hereby changed from 175 SY to 185 SY
 - d. Add Line # 0029, Item 3548000000-E, Section 866, Green Vinyl Coated Metal Terminal Post for 48" Chain Link Fence is hereby added with a quantity of 2.
 - e. Add Line # 0030, Item # 3542000000-E, Section 866, Green Vinyl Coated Metal Line Post for 48" Chain Link Fence is hereby added with a quantity of 10.

Sincerely,



David Cates, PE
Project Manager (Public Works Department)

ITEM SHEETS

Line #	Item #	Sec #	Description	Quantity		Unit Cost	Amount
0001	0000100000-N	800	MOBILIZATION	1.00	LS	\$	\$
0002	0043000000-N	226	LUMP SUM GRADING	1.00	LS	\$	\$
0003	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	40.00	LF	\$	\$
0004	1077000000-E	SP	#57 STONE FOR TREE-PROTECTION	5.00	TON	\$	\$
0005	1099500000-E	505	SHALLOW UNDERCUT	50.00	CY	\$	\$
0006	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	30.00	TON	\$	\$
0007	1121000000-E	520	AGGREGATE BASE COURSE (ABC STONE)	120.00	TON	\$	\$
0008	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1.00	EA	\$	\$
0009	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE **	1.00	EA	\$	\$
0010	2396000000-N	840	FRAME WITH COVER, STD 840.54	1.00	EA	\$	\$
0011	2418000000-E	SP	FRAME WITH GRATES, DRIVEWAY DROP INLET	36.00	LF	\$	\$
0012	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	1.00	EA	\$	\$
0013	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	200.00	LF	\$	\$
0014	2591000000-E	848	4" CONCRETE SIDEWALK	689.00	SY	\$	\$
0015	2605000000-N	848	CONCRETE CURB RAMP	11.00	EA	\$	\$
0016	2612000000-E	848	6" CONCRETE DRIVEWAY, 6" CONCRETE SIDEWALK & 6" CONCRETE SLOPE PROTECTION W/ 6" CURB	185.00	SY	\$	\$
0017	2830000000-N	858	ADJUSTMENT OF MANHOLES	1.00	EA	\$	\$
0018	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	4.00	EA	\$	\$
0019	2893000000-N	859	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX WITH MANHOLE	1.00	EA	\$	\$
0020	3524000000-E	SP	VINYL COATED CHAIN LINK FENCE, 4'	100.00	LF	\$	\$
0021	3691000003-N	SP	CURB INLET SILT INTERCEPTOR	5.00	EA	\$	\$
0022	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	1.00	LS	\$	\$
0023	5648000000-N	1515	RELOCATE WATER METER	1.00	EA	\$	\$
0024	5672000000-N	1515	RELOCATE FIRE HYDRANT	1.00	EA	\$	\$

0025	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	1.00	EA	\$	\$
------	--------------	------	--------------------------	------	----	----	----

Line #	Item #	Sec #	Description	Quantity		Unit Cost	Amount
0026	6000000000-E	1605	TEMPORARY SILT FENCE	420.00	LF	\$	\$
0027	6084000000-E	1660	SEEDING & MULCHING	4840	SY	\$	\$
0028	411610000-N	904	RELOCATE EXISTING SIGN	3.00	EA	\$	\$
0029	3548000000-E	866	GREEN VINYL COATED METAL TERMINAL POST FOR 48" CHAIN LINK FENCE	2.00	EA	\$	\$
0030	3542000000-E	866	GREEN VINYL COATED METAL LINE POST FOR 48" CHAIN LINK FENCE	10.00	EA	\$	\$