

**EB-5514 (SW-39) Unit Price Bid Worksheet**

Line #	Item Number	Sec #	Description	QUANTITY	Unit	Unit Cost	Amount
0001	0000100000-N	801	MOBILIZATION	1	LS		
0002	0000400000-N	801	CONSTRUCTION SURVEYING	1	LS		
0003	0043000000-N	226	GRADING	1	LS		
0004	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	330	SY		
0005	0163000000-E	250	REMOVAL OF EXISTING CONCRETE PAVEMENT	480	SY		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	25	TON		
0007	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	317	SY		
0008	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	315	LF		
0009	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	529	LF		
0010	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	32	LF		
0011	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	37	LF		
0012	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	37	LF		
0013	0453000015-E	310	15" PIPE END SECTION	2	EA		
0014	0453000018-E	310	18" PIPE END SECTION	1	EA		
0015	0453000024-E	310	24" PIPE END SECTION	1	EA		
0016	0995000000-E	340	PIPE REMOVAL	108	LF		
0017	0996000000-N	350	PIPE CLEAN-OUT	8	EA		
0018	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	510	TON		
0019	1121000000-E	520	AGGREGATE BASE COURSE	117	TON		
0020	1220000000-E	545	INCIDENTAL STONE BASE FOR DRIVEWAYS	232	TON		
0021	1297000015-E	607	MILLING ASPHALT PAVEMENT, 1.5"DEPTH	2413	SY		
0022	1491000000-E	610	ASP CONC BASE CRS B25.0C	487	TON		
0023	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	189	TON		
0024	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	397	TON		
0025	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	35	TON		
0026	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	11	EA		
0027	2308000000-E	840	MASONRY DRAINAGE STRUCTURES (greater than 5')	3	LF		
0028	2352000000-N	840	FRAME WITH GRATE, STD 840.03	11	EA		
0029	2354000000-N	840	FRAME WITH GRATE, STD 840.22	1	EA		
0030	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1856	LF		
0031	2591000000-E	848	4" CONCRETE SIDEWALK	1036	SY		
0032	2591000006-E	848	6" CONCRETE SIDEWALK	493	SY		
0033	2605000000-N	848	CONCRETE CURB RAMP	17	EA		
0034	2612000000-E	848	6" CONCRETE DRIVEWAY	1115	SY		
0035	2830000000-N	858	ADJUSTMENT OF MANHOLES	5	EA		
0036	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	15	EA		
0037	3628000000-E	876	RIP RAP, CLASS I	4	TON		
0038	3649000000-E	876	RIP RAP, CLASS B	5	TON		
0039	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	22	SY		
0040	3691000004-N	SP	GENERIC EROSION CONTROL ITEM (Curb Inlet Silt Interceptor)	13	EA		
0041	3691000005-N	SP	GENERIC EROSION CONTROL ITEM (Rock Inlet Sediment Trap Type C)	3	EA		
0042	4025000000-E	901	CONTRACTOR FURNISHED, TYPE E SIGN	19	SF		
0043	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	39	LF		
0044	4102000000-N	904	SIGN ERECTION, E	3	EA		
0045	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	1	LS		
0046	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3234	LF		
0047	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	1148	LF		
0048	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	252	LF		
0049	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	16	EA		
0050	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	2	EA		

Line #	Item Number	Sec #	Description	QUANTITY	Unit	Unit Cost	Amount
0051	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	337	LF		
0052	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	70	LF		
0053	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	227	LF		
0054	5648000000-N	1515	RELOCATE WATER METER	5	EA		
0055	5686500000-E	1515	WATER SERVICE LINE (ADJUSTMENT)	180	LF		
0056	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	3	EA		
0057	5768500000-E	1520	SEWER SERVICE LINE (ADJUSTMENT)	180	LF		
0058	6000000000-E	1605	TEMPORARY SILT FENCE	555	LF		
0059	6075000712-E	1651	SELECTIVE TREE REMOVAL, 7"-12"	7	EA		
0060	6075001318-E	1651	SELECTIVE TREE REMOVAL, 13"-18"	7	EA		
0061	6075001924-E	1651	SELECTIVE TREE REMOVAL, 19"-24"	2	EA		
0062	6075003699-E	1651	SELECTIVE TREE REMOVAL, > 36"	5	EA		
0063	6084000000-E	1660	SEEDING & MULCHING	2	ACR		
0064	6890000000-E	SP	CONCRETE STEPS	1	CY		
0065	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	2475	LF		
0066	7648000000-N	1746	RELOCATE EXISTING SIGNS AND MAILBOXES	26	EA		
0067	7980000000-N	SP	GENERIC SIGNAL ITEM (ADJUSTMENT OF SIGNAL JUNCTION BOXES)	2	EA		
						<b>Total</b>	