



May 17, 2021

To: Prospective Bidders

Subject: Addendum Two: Changes to the unit cost bid items and answer to questions.

Project: Trails Repair 2021 (SW-80)

This Addendum corrects the following for the subject referenced contract:

- **Changes to the unit cost bid items.**

This addendum revises the bid items to include the changes/additions below:

- 1) In line item #7 Asphalt patching using B25.0C; Undercut and Milling are incidental. language has been revised.

| | | | |
|---|---|----|-------|
| 7 | Asphalt Patching using B25.0C (Undercut & Milling are Incidental) | TN | 5,400 |
|---|---|----|-------|

- 2) A line item for Incidental Milling (up to a depth of 3") has been added.

| | | | |
|---|--|----|-------|
| 8 | Incidental Milling (up to a depth of 3") | SY | 1,000 |
|---|--|----|-------|

The incidental milling will be used as needed and as determined by the City’s project manager.

- **Answers to questions:**

Q) Are track milling machines allowed on trails?

A) Big machines or any machine that might cause damage to the existing asphalt surface are not allowed. We will not dictate means, if the contractor wants to use a milling machine and the trail asphalt surface can handle it then we will discuss it with the contractor.

The revised unit price bid sheet is attached to this addendum and posted on the project webpage at the following link:

<https://durhamnc.gov/4494>



| SW-80 TRAILS REPAIR 2021 | | | | | |
|-----------------------------|---|-------|----------|---------------|------|
| Item No. | Item Name | Units | Quantity | Unit Price \$ | Cost |
| 1 | Shoulder Grading | SY | 24,008 | | |
| 2 | Geotextile Fabric | SY | 22,007 | | |
| 3 | ABC Stone | TN | 1,800 | | |
| 4 | #57 Stone | TN | 780 | | |
| 5 | Asphalt Concrete Surface Course, Type 9.5B | TN | 9,600 | | |
| 6 | Asphalt Binder for Plant Mix, Grade PG 64-22 | TN | 720 | | |
| 7 | Asphalt Patching using B25.0C (Undercut & Milling are Incidental) | TN | 5,400 | | |
| 8 | Incidental Milling (up to a depth of 3") | SY | 1,000 | | |
| 9 | Drainage Ditch Excavation | CY | 210 | | |
| 10 | Rip Rap, Class A | TN | 62 | | |
| 11 | Rip Rap, Class B | TN | 62 | | |
| 12 | Rip Rap, Class 1 | TN | 84 | | |
| 13 | Rip Rap, Class 2 | TN | 104 | | |
| 14 | Geotextile for Drainage (Type 2) | SY | 520 | | |
| 15 | Geotextile for Soil Stabilization (Type 4) | SY | 520 | | |
| 16 | Matting for Erosion Control | SY | 2,594 | | |
| 17 | Seeding and Mulching | SY | 2,594 | | |
| 18 | Coir Fiber Matting | SY | 2,594 | | |
| 19 | 15-inch R.C. Pipe Culverts, Class III (0 to 5-feet) | LF | 168 | | |
| 20 | 18-inch R.C. Pipe Culverts, Class III (0 to 5-feet) | LF | 168 | | |
| 21 | 24-inch R.C. Pipe Culverts, Class III (0 to 5-feet) | LF | 168 | | |
| 22 | 15-inch Pipe End Section | EA | 14 | | |
| 23 | 18-inch Pipe End Section | EA | 14 | | |
| 24 | 24-inch Pipe End Section | EA | 14 | | |
| 25 | Reinforced Endwalls | CY | 31 | | |
| 26 | Curb Ramps (Removal is incidental) | EA | 96 | | |
| 27 | Yellow Paint Marking 4" | LF | 60,020 | | |
| 28 | Seeding & Mulching | SY | 31,980 | | |
| 29 | Traffic Control (Message boards are incidental) | LS | 1 | | |
| 30 | Mobilization (5%) | LS | 1 | | |
| TOTAL AMOUNT FOR BID | | | | | |

This change supersedes all previously posted unit price bid tables.

Please let me know if you have any questions.

Sincerely,

Bayan M. Alzubi, EI
 Engineer/Project Manager – Contract Management
 Department of Public Works – City of Durham
 101 City Hall Plaza, Ste. 3100, Durham, NC 27701
Bayan.Alzubi@durhamnc.gov