



SW-80 TRAILS REPAIR 2021						
Item No.	Item Name	Units	Quantity	Unit Price \$	Cost	
1	Shoulder Grading	SY	24,008			
2	Geotextile Fabric	SY	22,007			
3	ABC Stone	TN	1,800			
4	#57 Stone	TN	780			
5	Asphalt Concrete Surface Course, Type 9.5B	TN	9,600			
6	Asphalt Binder for Plant Mix, Grade PG 64-22	TN	720			
7	Asphalt Patching using B25.0C (Undercut & Milling are Incidental)	TN	5,400			
8	Incidental Milling (up to a depth of 3")	SY	1,000			
9	Drainage Ditch Excavation	CY	210			
10	Rip Rap, Class A	TN	62			
11	Rip Rap, Class B	TN	62			
12	Rip Rap, Class 1	TN	84			
13	Rip Rap, Class 2	TN	104			
14	Geotextile for Drainage (Type 2)	SY	520			
15	Geotextile for Soil Stabilization (Type 4)	SY	520			
16	Matting for Erosion Control	SY	2,594			
17	Coir Fiber Matting	SY	2,594			
18	15-inch R.C. Pipe Culverts, Class III (0 to 5-feet)	LF	168			
19	18-inch R.C. Pipe Culverts, Class III (0 to 5-feet)	LF	168			
20	24-inch R.C. Pipe Culverts, Class III (0 to 5-feet)	LF	168			
21	15-inch Pipe End Section	EA	14			
22	18-inch Pipe End Section	EA	14			
23	24-inch Pipe End Section	EA	14			
24	Reinforced Endwalls	CY	31			
25	Curb Ramps (Removal is incidental)	EA	96			
26	Yellow Paint Marking 4"	LF	60,020			
27	Seeding & Mulching	SY	34,573			
28	Traffic Control (Message boards are incidental)	LS	1			
29	Mobilization (5%)	LS	1			
				TOTAL AMOUNT FOR BID		