



June 22, 2021

To: Prospective Bidders

Subject: Addendum Seven: Changes to the unit cost bid.

Project: Trails Repair 2021 (SW-80)

This Addendum corrects the following for the subject referenced contract:

- **Changes to the unit cost bid items.**

This addendum revises the bid items to include the changes/additions below:

1) The following line items have been added to the bid sheet:

2	Aggregate Shoulder Borrow	TN	2,000
9	Concrete Sidewalk (4") (Includes 6" ABC Stone)	SY	125
10	Concrete Sidewalks, Driveways, and Aprons (6") (Includes 6" ABC Stone)	SY	125

The revised unit price bid sheet is attached to this addendum and posted on the project webpage at the following link:

<https://durhamnc.gov/4494>

**This change supersedes all previously posted unit price bid tables.**

SW-80 TRAILS REPAIR 2021					
Item No.	Item Name	Units	Quantity	Unit Price \$	Cost
1	Shoulder Grading	SY	24,008		
2	Aggregate Shoulder Borrow	TN	2,000		
3	Geotextile Fabric	SY	22,007		
4	ABC Stone	TN	750		
5	#57 Stone	TN	780		
6	Asphalt Concrete Surface Course, Type 9.5B	TN	9,600		
7	Asphalt Binder for Plant Mix, Grade PG 64-22	TN	720		
8	Asphalt Patching using B25.0C (Undercut & Milling are Incidental)	TN	5,400		
9	Concrete Sidewalk (4") (Includes 6" ABC Stone)	SY	125		
10	Concrete Sidewalks, Driveways, and Aprons (6") (Includes 6" ABC Stone)	SY	125		
11	Incidental Milling (up to a depth of 3")	SY	1,000		
12	Drainage Ditch Excavation	CY	210		
13	Rip Rap, Class A	TN	62		
14	Rip Rap, Class B	TN	62		
15	Rip Rap, Class 1	TN	84		
16	Rip Rap, Class 2	TN	104		
17	Geotextile for Drainage (Type 2)	SY	520		
18	Geotextile for Soil Stabilization (Type 4)	SY	520		
19	Matting for Erosion Control	SY	2,594		
20	Coir Fiber Matting	SY	2,594		
21	15-inch R.C. Pipe Culverts, Class III (0 to 5-feet)	LF	168		
22	18-inch R.C. Pipe Culverts, Class III (0 to 5-feet)	LF	168		
23	24-inch R.C. Pipe Culverts, Class III (0 to 5-feet)	LF	168		
24	15-inch Pipe End Section	EA	14		
25	18-inch Pipe End Section	EA	14		
26	24-inch Pipe End Section	EA	14		
27	Reinforced Endwalls	CY	31		
28	Curb Ramps (Removal is incidental)	EA	96		
29	Yellow Paint Marking 4"	LF	60,020		
30	Seeding & Mulching	SY	34,573		
31	Traffic Control ( Message boards are incidental)	LS	1		
32	Mobilization (5%)	LS	1		
				<b>TOTAL AMOUNT FOR BID</b>	

Please let me know if you have any questions.

Sincerely,

Bayan M. Alzubi, EI  
 Engineer/Project Manager – Contract Management  
 Department of Public Works – City of Durham  
 101 City Hall Plaza, Ste. 3100, Durham, NC 27701  
[Bayan.Alzubi@durhamnc.gov](mailto:Bayan.Alzubi@durhamnc.gov)