

ADDENDUM #1 - ST-320: STREET REPAIR & REPAVING 2022

Item No.	Item Name	Units	BID Quantity	BID Unit Price	BID Cost
1	Asphalt Binder for Plant Mix - Grade PG64-22	TON	3,370		
2	Asphalt Surface Course - Type S9.5B	TON	38,110		
3	Asphalt Surface Course - Type S9.5C	TON	5,420		
4	Asphalt Intermediate Course - Type I19.0C	TON	9,190		
5	Removal of Pavement Structure- 0 to 1.5"	SY	10,120		
6	Removal of Pavement Structure - >1.5" to 3"	SY	199,080		
7	Removal of Pavement Structure - >3" to 4.5"	SY	36,580		
8	Removal of Pavement Structure - >4.5" to 6"	SY	49,680		
9	Incidental Milling	SY	3,450		
10	Asphalt Patching (Structure Removal is Incidental)	TON	3,920		
11	Water Valve Adjustment - Ring	EA	5		
12	Water Valve Adjustment - Manual	EA	50		
13	Water Valve Adj, Frame&Cover Replace	EA	90		
14	Manhole Adjustment - Ring	EA	30		
15	Manhole Adjustment - Manual	EA	250		
16	Manhole Adj, Frame&Cover Replace	EA	150		
17	R/R Standard Curb and Gutter	LF	100		
18	R/R Driveway Apron	SY	100		
19	Pavement Edge Repair	TN	300		
20	Aggregate Shoulder Borrow	TN	200		
21	Shoulder Borrow	CY	100		
22	Seeding & Mulching	SY	950		
23	Thermo Yellow Double Center 4" 120 mil	LF	20,810		
24	Thermo Pvmt Marking Lines 4" 90 mil	LF	7,990		
25	Thermo Pvmt Marking Lines 4" 120 mil	LF	7,990		
26	Thermo Pvmt Marking Lines 8" 90 mil	LF	1,500		
27	Thermo Pvmt Marking Lines 8" 120 mil	LF	1,500		
28	Thermo Pvmt Marking Lines 24" 120 mil	LF	5,160		
29	Thermo Alphanumeric Characters	EA	20		
30	Thermo Turn/Straight Arrow	EA	15		
31	Thermo Combo Turn/Straight Arrow	EA	5		
32	Thermoplastic Bicycle Symbol	EA	10		
33	Thermoplastic Bicycle Straight Arrow	EA	10		
34	Thermoplastic Sharrow	EA	5		
35	Block Border Speed Hump	EA	17		
36	Inductive Loop Sawcut	LF	3,600		
37	Variable Message Boards	EA	30		
38	Traffic Control	LS	1		
39	Mobilization	LS	1		
TOTAL BID AMOUNT					

ACKNOWLEDGMENT OF ADDENDA

SIGNATURE: _____

NUMBER 1: _____

DATE: _____